

## Flow Options

- HT – Hydrostatic test ASTM-E-1003-95 and certificate.
- XR – X-ray inspection test and certificate.
- PI – Positive material identification test (PMI) and certificate.
- DY – Dye penetrans test ASTM-E-1220-05 and certificate.
- NT – Hardness test and certificate.
- FC – Flow calibrations and certificate ( max. No. Reynold )
- FE – Flow calibrations at specific flow values, graphics and hysteresis and certificate.
- AA - AGA3 / API-14.3.2 set. Flow conditioner, temperature sensor, flow element and Hart protocol transmitters supplied in a calibrated section.
- TC – Temperature elements and thermowells for mass flow.
- AS – Assembled set of flow elements, manifolds, transmitters and pots.
- AR – Average D.P. tap rings.
- FT – Flow conditioner
- CR – Carrier ring for ASME 16.5 flanges.
- IP – Boroscopic inspection port according to ASME.
- M3 – Manifold 2 ways, 3 valves (please specify material).
- RV – Forged root valves (please specify).
- CP – Condensing pots (please specify material).
- DP – Differential pressure flow transmitter (Hart communication).